

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Menominee (County) Located In: Corner Code #
1. Public Land Survey T 41N R 26W G04
T 41N R 26W J03
2. Property Controlling Section S T R
S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. , Recorded Plat
5. Private Claims

8/14/2014
Jeremy J. Pipp, in a field survey on 8/12/2014 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G04) Quarter corner common to Sections 9 and 10. 1852: E.C. Martin, DS. Set quarter section post
witnessed by Tamarack 8 S30E 17 links (11.22'), Tamarack 8 N63W 19 links (12.54'). No evidence
of subsequent establishment.
(J03) Quarter corner common to Sections 2 and 11. 1852: E.C. Martin, DS. Set quarter section post
witnessed by Cedar 10 S30E 9 links (5.94'), Fir 14 N62W 26 links (17.16'). No evidence of
subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G04) No evidence of original survey. Found recent wood post S28E 4.5 feet from calculated position
with no other post points or corresponding original evidence. Corner position reestablished by
single proportionate measurement between the Northwest corner and the Southwest corner of Section
3. Position is accepted as a careful and faithful REESTABLISHMENT of the position of the original
corner.
(J03) No evidence of original survey. Corner position reestablished by single proportionate
measurement between the Southwest corner and the Southeast corner of Section 2. Position is
accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G04) DNR monument (J03) DNR monument
7" Tamarack N52E 31.30' (1/4S,NBT) 14" Hemlock N30E 45.66' (1/4S,NBT)
6" Tamarack S02E 9.66' (1/4S,NBT) 13" Hemlock S89E 24.96' (1/4S,NBT)
6" Tamarack N61W 81.41' (1/4S,NBT) 12" Cedar S02E 18.52' (1/4S,NBT)
7" Tamarack N19W 36.57' (1/4S,NBT) 16" Hemlock N58W 28.72' (1/4S,NBT)

All trees are blazed, scribed, painted, and signed. Measurements are to nail in
side of tree, bearings are magnetic. A Metal sign post was set North 1.5 feet.
Signed by Jeremy J. Pipp Date August 25, 2014

Surveyor's Michigan License No. 50447
For the Michigan Department of Natural Resources



Table with 13 rows and 13 columns (A-M). Contains a grid of numbers 1-36 and a single black dot at row 3, column J.

Register of Deeds Stamp & File Number