

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 22 N. R. 6 W. ●	G-7; G-8; G-9; H-9
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-7 Set corner at the apparent  $\angle$  intersection of county roads. No previous monument could be located.
- G-8 Set corner by proportionate measurement M.P.O.L. between section corners. Can locate no previous corner monument.
- G-9 Set corner in line w/fence W, in  $\angle$  of N-S county road. Could find no other monument.
- H-9 Set corner on line between section corners, in line with fence south. Considered best evidence of any previous corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7	G-8	G-9
Set DNR Monument	Set 5/8" rod w/RLS Cap	Set DNR Monument
Teleph. Pole N43°W 74.59	4" Maple N30°W 22.8	7" Oak N56°E 40.5
Power Pole S34°W 60.60	6" Birch in clump N45°E 59.0	6" Oak S40°E 40.0
	Cedar Post East 27'	
		H-9
		Set DNR Monument
		2" Spruce S49°W 29.6
		2" W. Pine N85°W 8.0
		1" Birch S73°E 9.8

SIGNED BY Kenneth J. Ostling

DATE 9/4/80

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_


CHIEF OF SURVEY PARTY

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

DATE \_\_\_\_\_



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

MISSAUKEE COUNTY