

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1215

For corners in

Missaukee County Located In: Corner Code #
 (County)

1. Public Land Survey T 23N R 6W M-6
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

LIBER 315 PAGE 1118
MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 29 1997 1:25 P.M.

Paulyn Flare
 REGISTER
 Register of Deeds Stamp & File
 Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-6) 1839 GLO survey set quarter post section 13; 9" diameter Hemlock named corner
 1913 Iron stake, county survey records
 1985 Robert F. Mitchell LCRC, #698; Fd. 1" iron rod, raised w/ 1/2" rerod w/ cap
 N25W 5" Elm 39.68', S15E 10" Elm 28.28', N65E 5" Wild Cherry 61.38', N45W Road Sign Post 34.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6) Corner common to Section 13, T23N, R6W and Section 18, T23N, R5W. Found 1/2" rerod/cap over a 1" iron rod.
 Corner falls in centerline of E&W road and 5' East of N&S road.

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6) Set Missaukee County Monument on existing corner.


N30W 39.71' 13" elm
 S14E 28.01' 24" elm
 N74E 61.92' 6" twin cherry
 N27E 83.35' power pole
 S40E 40.80' fence corner post

Peer Group Reviewed and Approved

Date: 12-8-97
J. Doan Geers
 J. Doan Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema
 Surveyor's Michigan License No. 24617

Date 12-2-97



SURVEY & REMONUMENTATION

JAN 16 1998

SECTION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995