

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 7 W.	I-7; E-6; E-7
2. PROPERTY CONTROLLING IN SECTION 17	T. 24 N. R. 7 W.	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. R. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 3, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~as a description of original monument and accessories and/or subsequent restoration~~

C. (continued)

7
Set 5/8"x36" rerod w/RLS Cap &
cedar post w/loc. tag
9" Maple N53°W 15.1
9" Maple N10°E 26.9
23" Maple N60°E 73.9
N-S Trail Due E 100'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-7 Fd. 1" pipe surrounded with stones; 1.5' deep from 1909 wit. by J. G. Cavanagh; Cor. fn. post (still standing), N51°E, 45.3'. Raised with 1/2" rerod.

E-6 Fd. conc. mon. by Cavanagh (1909). Corner used in MSHD survey. Corner is 1'± E of center of old N-S grade.

E-7 Fd. 1" pipe as set by MSHD over fd. conc. mon. (Mon. by Cavanagh in 1909).

7 Set 1/8 corner per standard BLM instructions. Corner drove in roots of SW edge of 12" Maple stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7	E-6	E-7
Fd. 1" pipe & raised with 1/2"x18" Rerod	Fd. 1" pipe in conc. (buried 0.4) added ced. post w/loc. tag	Fd. 1" pipe (buried 0.1) & broken pieces of conc. mon.
P. Pole w/transf. S15°E 123.97	*12" Ash S83°E 15.52	12" Maple N34°E 18.68
P. Pole S72°E 101.45	* 8" Elm S46°W 18.37	7" Tw. Maple S72°E 9.87
Ctr. 1 1/2" pipe rd. sign N35°W 50.45	* 9" Maple N32°W 17.75	5" Oak N46°W 38.50
Ctr. E-W b'top rd. Due N 2'	5" Maple N61°E 37.2	Set ced. post Due E 16.5
Ctr. gravel rd. S Due E 8'±	*MSHD witnesses	
Ctr. gravel rd. N Due E 4'±		

SIGNED BY Carl F. Roser

DATE 02-17-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____

DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MISSAUKEE COUNTY
PIONEER TOWNSHIP