

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>29</u> N. R. <u>3</u> E.	<u>C-6; D-5; D-7; E-6</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 20, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-6 Replaced ½" rebar. DeLaMater record states he found both OBTS.
D-5 Found ½" rerod and G. F. DeLaMater's witnesses.
D-7 Set from southwest OBT (good face) and northwest DeLaMater witness.
E-6 Found ½" rerod and both DeLaMater NBTs with witness caps in face.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7	D-5	D-7
DNR Mon. & Post	Set DNR Mon.	DNR Mon.
9" J. Pine N22E 30.15'	11" Cedar N70W 28.35'	16" Bl. Oak N16W 51.4'
9" J. Pine S58E 42.4'	7" Cedar N54E 16.1'	11" R. Oak N13E 54.8'

E-6
DNR Mon. & sq. 8" cedar post
11" Cedar N75W 21.9'
9" Cedar N63E 30.0'
5" Cedar N10W 4.6'



SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____