

**SURVEY &
REMONUMENTATION**

Montmorency County Remonumentation Liber 00012 Page 0135

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-10-1994 14:13:50

A. PANGAN-MCELROY
REGISTER OF DEEDS

For corners in **COMMISSION**

Montmorency
(County)

Located In:

Corner Code =#

Montmorency Township

1. Public Land Survey

T 32 N R 3 E

A-7

T R

T R

T R

T R

**APPROVED BY
PEER GROUP**

AUG 05 94

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Don Marlatt, in a field survey on November 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-7) S.W. Cor. Sec. 18, T 32 N, R 3 E

Original post set by Hiram Burnham July 1850. (Pine Post).

14" Y. Pine N 50° W 18 links

16" Y. Pine S 65° W 16 links

Schaaf - DNR Survey - No Date.

DNR Survey - Sec. 19, T 32 N, R 3 E in 1958 & 1989.

Land Corner Record - DNR - 1958.

D. Porter - Recorded Act 74, L. 1, P. 397 on July 22, 1987.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-7) S.W. Cor. Sec. 18, T 32 N, R 3 E

Found DNR Monument - 1" pipe with 4" cap in East wheel track.

Tw. 10" Oak N 89° W 17.28'

10" W. Pine S 56° E 39.47'

6" W. Pine S 21° E 40.2'

10" Oak S 36° W 48.01'

No evidence of original corner.

Accepted as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-7) S.W. Cor. Sec. 18, T 32 N, R 3 E

Left DNR Monument in place.

13" W. Pine S 60° E 39.45'


10" W. Pine S 25° E 40.22'

13" Maple S 30° W 48.0'

12" Maple N 85° W 54.92'

8" Tw. Maple West 17.05'

Witnesses marked with a 30 penny spike & I.D. tag #18660.



Signed by

Donald E Marlatt

Date

11-9-1994

Surveyor's Michigan License No.

18660.