

SURVEY & REMONUMENTATION

LIBER 15292 PG 359

MAR 15 1995 04 19 71

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OAKLAND
(County)

COMMISSION

Located in: WATERFORD

Corner Code #

1. Public Land Survey T 3 N R 9 E K-7
2. Property Controlling S T R
3. Miscellaneous S T R
- Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

7.00 MISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:07 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12.30.94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number


I, THOMAS M. SMITH, in a field survey on NOVEMBER 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
POST, G.L.O. NO L.C.R.C. RECORDED.
1817

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A LARGE IRON PIPE WITH A 3"+/- FITTING ON TOP IN A MONUMENT BOX IN THE CENTERLINE OF SCOTT LAKE ROAD. MEASURED DISTANCES SOUTH & EAST. VERIFY THIS CORNER WITH THE PLAT OF LaSALLE PARK SUBDIVISION.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7: I LEFT THE IRON PIPE WITH FITTING IN THE MONUMENT BOX.

- S 55 E. 119.35' to remon tag N.E. sign leg post.
- S 75 W. 115.42' to remon tag N, side 10" oak.
- N 80 W. 70.13' to remon tag N.E. side 36" oak.
- N 40 W. 117.30' to remon tag N.E. side 36" oak.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by Surveyor's Michigan License No. 31606

Date DECEMBER 19, 1994