

SURVEY &
REMONUMENTATION

94 193400

LIBER 14833 PG 156

Compliance with
ACT 345, P.A. 1990

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 1-19-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

For corners in
Oakland

COMMISSION

	Located In:		Corner Code #
(County)	5N	11E	A-2
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling In Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 JUL 94 7:38 A.M. RECEIPT# 1A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Bruce Antcliff, in a field survey on November 12, 1993,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-2	GLO	LCRC L.8273 P.790 (1982)
	Post	1/2" iron rod capped RLS 16045
		S 20° E - 14.30' 10" Ash
		S 20° W - 36.45' 20" Maple
		N 30° E - 7.23' 14" Ash
		N 30° W - 36.43' 21" Ash

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 Found 1/2" iron bar (no cap) at center line of dirt 2-track trail and fence line East. Checks split of N & S fences. Fence running
West is 3' North. Check meas. North to NW Corner Section 6 as shown in Survey L. 5905, P. 760 (1972).
Checks the following witnesses:

S 20° E - 14.30' Pk Nail SW Face 10" Ash
N 30° E - 7.23' Pk Nail W Face 14" Ash
N 30° W - 36.43' Nail NE Face 24" Ash


Common corner to Section 1 T5N, R10E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 The selected location of a corner, although not established by an original government survey,
is accepted as the best available evidence of the position of the corner.

Set 4" concrete monument with standard Oakland County cap.

P.K. Nail and Brass Tag in SW Face 24" Ash N 33° W - 35.71'
P.K. Nail and Brass Tag in N Face 14" Ash S 76° W - 24.02'
P.K. Nail and Brass Tag in W Face 22" Maple S 20° W - 36.61'
P.K. Nail and Brass Tag in W Face Tri-12" Ash N 20° E - 24.80'



Signed by Bruce Antcliff
Surveyor's Michigan License No. 25826

Date 7-11-94