

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 15 N. R. 18 W.	K-1; K-2; K-3
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION 1	T. 15 N. R. 18 W. and 1987.06 N of L-2)	XX (667.85 S of L-1
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 8, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on September 8, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~At this point of the recordation, no corner evidence was found or method applied in restoring or re-establishing corner:~~
C. (continued)

XX
Set $\frac{1}{2}$ "x3/8"x18" iron & cedar
post w/loc. tag
6" W. Oak S85°E 7.7
34" W. Oak S05°E 68.0
E N-S Trail Due W 9'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1 Reestablished sec. corner to Sec. 1 & 2 (closing corner) T15N-R18W on line between fd. N $\frac{1}{4}$ Sec. 2 & NE Sec. 1 & at record U.S. distance E (50 links) of standard corner.
- K-2 Reestablished $\frac{1}{4}$ corner on line between sec. corners to N & S and at proportionate measurements to U.S.
- K-3 Fd. 1"x8" bolt & stump remains (roots) of two old Co. Rd. Comm. elm witnesses. Corner falls in approx. center of E-W gravel rd. & is in line w/old fence remains to N along edge of hardwoods.
- XX Established SW corner of N $\frac{1}{2}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$ of Sec. 1, 667.85 S of N $\frac{1}{4}$ corner & 667.85 N of N 1/16 on N-S $\frac{1}{4}$ line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1	K-2	K-3
Set DNR monument & cedar post	Set DNR monument & cedar post	Fd. bolt, added 1 $\frac{1}{4}$ "x23" iron pin
8" R. Oak S35°E 27.3	6" W. Pine N20°W 44.7	35" Maple N45°W 102.9
7" B. Oak S10°W 17.9	5" W. Pine S25°W 24.5	Power Pole S05°E 49.36
SW Sec. 36 (T16N-R18W)		Set cedar post w/loc. tag
N87°53'W 33.0		Due N 33'

SIGNED BY Carl F. Roser 5-23-77 DATE


SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

GOLDEN TOWNSHIP
OCEANA COUNTY