

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:26

For corners in

COMMISSION  
OTTAWA

Located In:

Corner Code #

*D. J. Vugteveen*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

- |                         |   |    |   |     |                |     |
|-------------------------|---|----|---|-----|----------------|-----|
| 1. Public Land Survey   | T | 6N | R | 13W | E-7 (SE        | cor |
|                         | T |    | R |     | Section 17)    |     |
|                         | T |    | R |     | Georgetown Twp |     |
|                         | T |    | R |     |                |     |
| 2. Property Controlling | S |    | T | R   |                |     |
| in Section              | S |    | T | R   |                |     |
| 3. Miscellaneous        | S |    | T | R   |                |     |
| Property in Sec.        | S |    | T | R   |                |     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-7 LCRC Liber 3, Page 167  
1-1/4" Iron Pipe  
10" W. Cherry S 10 E 12.23'  
4" Ash S30W 4.12'  
10" Ash N40W 25.10'  
Twin 6" Pear S70E 24.40'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found 1 1/4" iron pipe on tree line East and accepted as a careful and faithful perpetuation of the position of the original corner  
10" W. Cherry S10E 12.22'  
4" Ash S30W 4.12'  
10" Ash N40W 25.13'  
Twin 6" Pear S70E 24.54'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Placed 3/4" X 36" solid rod inside 1 1/4" pipe with Ottawa County Remon Cap

Set Ottawa County Remon Tag & Nail in N side 8" Ash S30W 3.91'  
Set Ottawa County Remon Tag & Nail in SW side 10" Ash N40W 25.13'  
Set Ottawa County Remon Tag & Nail in W side 10" W. Cherry S10E 12.21'  
Set Ottawa County Remon Tag & Nail in N side 8" Twin Pear S70E 24.54'



Signed by

*Randal J. Vugteveen*

Date

Dec 6, 1993

Surveyor's Michigan License No.

28429