

SURVEY &
REMONUMENTATION

NOV 10 1993

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa
(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|------------|---|
| 1. Public Land Survey | T 6N R 13W | H-5 (S 1/4 cor
Section 10)
Georgetown Twp |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling
in Section | S T R | |
| | S T R | |
| 3. Miscellaneous
Property in Sec. | S T R | |
| | S T R | |

RECORDED

1993 SEP 29 PM 3:14

Randal J. Vugteveen
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Randal J. Vugteveen, in a field survey on July 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-5 1/4 corner common to Sections 10 & 15 Georgetown

1/2" iron recorded 1974 Liber 2 Pg. 623
NE cor hse SW 90.45'
Nail in side 18" Oak SW 58.47'
Nail in side 26" Oak W 100.35'
Centerline of hydrant NE 37.92'

H-5 set capped iron re-established
PK N side service pole N80°E 26.11'
Centerline top hydrant N45°E 37.95'
PK Sly side p.pole S85°W 24.98'
Spike NW side 22" Oak S40°W 58.63'
NE cor house foundation S50°W 90.48'
NW cor house (to brick) S80°E 89.49'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 Found Exxel capped iron centerline 20th Ave. and accepted it as a careful and faithful perpetuation of the original corner

Found PK service pole N80°E 26.11'
Centerline top hydrant N45°E 37.95'
NE corner hse foundation S50°W 90.45'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 Replaced capped iron with 3/4" X 24" solid rod with Ottawa County Remon cap

Ottawa County Remon tag & nail N. side P. pole	N80°E	26.09'
Ottawa County Remon tag & nail S. side P. pole	S85°W	24.05'
Ottawa County Remon tag & nail NW side 22" Oak	S40°W	58.62'
NE corner foundation hse #2015 Mulberry	S50°W	90.45'
NW corner brick on duplex 7992 20th Ave.	S80°E	89.43'
Centerline top hydrant	N45°E	37.94'

Signed by

Randal J. Vugteveen

Date

Sept 20, 1993

Surveyor's Michigan License No.

28429

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, J.M. 871
REVISED MAY 14, 1975
REVISED JAN 1, 1983

