

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

RECORDED

94 DEC 15 AM 11:48

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

Douglas J. Koning
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R 15W	K-10
	T R	(W 1/4 cor., Sec.
	T R	25, Olive Twp.)
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Douglas J. Koning, in a field survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/of subsequent restoration:

K-10 Government Notes
Set Post May 1832
By Calvin Britain D.S.
Tamarack 6" S32°E 37 Links
Leo 5" S18°W 26 Links

L.C.R.C. Liber 1, Page 239 January 1972
K-10
Tel. Pole SE 77.46'
Tel. Pole SW 27.12'
Centerline gravel road W 1'
East and West Tel. line S 11.5'

L.C.R.C. Liber 1, Page 355 April 1972
F-10 Set Steel Bar Midway on Line
13'± N of Utility Lines

L.C.R.C. Liber 3, Page 203, November 19
K-10 Set Cast Iron Monument
Power Pole WSW 27.82'
Power Pole SE 78.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-10 Found Cast Iron Monument (Top Broke)
Found Nail & Tag NEly side Pwr Pole S30°E 78.06'
Found Nail & Tag N side Pwr Pole S70°W 27.87'
Monument is 0.10' W & 0.26' N of being midway and on line.
12.5' N. of Utility Lines.


P.A. 345 OTTAWA COUNTY
PEER APPROVED, 12/12/94

Kendall D. Nedewell

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-10 Cast Iron Monument (1' E of centerline 104th Ave., 13'± N of centerline Pwr Lines, 1' deep)
Set O.C. Remon Nail & Tag SWly side Pwr Pole S87°E 285.25'
Set O.C. Remon Nail & Tag W side Pwr Pole S30°E 77.99'
Set O.C. Remon Nail & Tag SEly side Pwr Pole S70°W 27.85'
Set O.C. Remon Nail & Tag Nly side Pwr Pole N90°W 334.19'



Signed by Douglas J. Koning
Surveyor's Michigan License No. 35995

Date November 14, 1994