

1993

COMM

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:30

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa
(County)

Located In: Robinson Township
Corner Code #

- | | | |
|-------------------------|---|----------------------|
| 1. Public Land Survey | T <u>7N</u> R <u>15W</u> | <u>E-6</u> |
| | T <u> </u> R <u> </u> | <u>W. 1/4 Corner</u> |
| | T <u> </u> R <u> </u> | <u>Section 16</u> |
| | T <u> </u> R <u> </u> | |
| 2. Property Controlling | S <u> </u> T <u> </u> R <u> </u> | |
| in Section | S <u> </u> T <u> </u> R <u> </u> | |
| 3. Miscellaneous | S <u> </u> T <u> </u> R <u> </u> | |
| Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | |

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Carl P. Englert Jr.

I, , in a field survey on November 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6 L.C.R.C. Liber 3, Page 272, 8/10/78
Fd. Concrete Monument'
Spike in side 14" Pak N 80 degrees E. 38.24'
Spike in side 14" Oak SE 45.76'
Spike in side 10" Pine N 75 degrees W 56.05'
C/L Culvert under Rd. 4' S of Corner

L.C.R.C. Liber 4, Page 161,
4/1/811
Fd. Conc. Mon., Set C.I.M.
12" Pepperidge NE 38.28'
9" Pine NW 36.04'
12" Aspen W.S.W. 33.96'
16" Oak S.E. 63.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found 4" Harrison Monument
with Broken Top and accepted
as a careful and faithful
perpetuation of the position
of the original corner.

Fd. 12" Aspen W.S.W. 33.96'
Spike in 14" Oak S.E. 45.76'
C/L Culvert 4'± S. of Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 4" Harrison Cast Iron Monument with Broken top in C/L 128th Avenue
O.C. Remon. Tag & Nail in S.W. side 12" Pine N. 37 degrees W. 60.48'
O.C. Remon. Tag & Nail in S. side 12" Aspen S. 70 degrees W. 33.95'
O.C. Remon. Tag & Nail in S.W. side 15" Oak S. 46 degrees E. 45.67'
O.C. Remon. Tag & Nail in N. side 15" Tw. Oak S. 81 degrees E. 32.64'
O.C. Remon. Tag & Nail in E. side P.P. N. 10 degrees E. 200.68'
(E.D.M.)

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date December 3, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1994

