

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 16 PM 1:01

For corners in

Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey T 8N R 16W M-8, E $\frac{1}{2}$ corner
T _____ R _____ Section 24
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS E. JOINER, in a field survey on 8-27-, 19 93,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:


Iron Pipe 1976 T.K.A.
West 49.95 Powerpole
E.S.E. 84.78 Powerpole
S.W. 53.18 6" Maple
East 33.00 Iron

Cast Iron Monument in Monument Box
Liber 4, Pg. 247 11-4-81
W.N.W. 49.48 Powerpole
S.W. 53.15 10" Maple
S.E. 91.20 Powerpole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found cast iron monument and accepted as a careful and faithful perpetuation of the
position of the original corner.

W.N.W. 49.48 Powerpole
S.W. 53.15 10" Maple
S.E. 91.20 Powerpole



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

O.C. Remon Cap Over Existing Cast Iron Monument	
O.C. Remon tag & nail in West side of 14" White Pine	AZ. 26° 36' 00" 69.55
O.C. Remon tag & nail in the East side of 12" Maple	AZ. 214° 42' 00" 52.65
O.C. Remon tag & nail in the South side of powerpole	AZ. 283° 11' 00" 49.84
Center of operating nut on hydrant	AZ. 92° 06' 00" 26.09

Signed by Thomas E. Joiner
Surveyor's Michigan License No. 18435

Date 8-31-93