

SURVEY &  
REMONUMENTATION

APR 29 1996

JUDITH D. ROEHM 10/26/95  
Ontonagon County 14:07  
LC 3/ 366 MEL Fee: 9.00  
Page 1 of 1

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON  
(County)

Located In:

Corner Code #

- |                         |      |      |     |
|-------------------------|------|------|-----|
| 1. Public Land Survey   | T 48 | R 42 | B-3 |
|                         | T    | R    |     |
|                         | T    | R    |     |
|                         | T    | R    |     |
| 2. Property Controlling | S    | T    | R   |
| in Section              | S    | T    | R   |
| 3. Miscellaneous        | S    | T    | R   |
| Property in Section     | S    | T    | R   |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner common to Section 6 & Section 7, T48N R42W.

I, Earl W. Applekamp, in a field survey on October 05, 19 95,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found  
as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor,  
August, 1848. Set Maple Post.

ORIGINAL BEARING TREES:

Tamarack 10" S60°W 98 links (64.68 feet)  
Tamarack 14" N38°W 44 links (29.04 feet)

Note: The original notes indicate the corner was set 40 chains East of SW

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Corner to be set  
at 37 chains.

No original evidence was found. I re-established the  $\frac{1}{4}$  Corner  
at a point 37.00 Chains East of the SW Corner of Section 6 and  
set a monument described at "C" below.

Research on file with the County Remonumentation Program Representative.


PEER GROUP APPROVED

Earl W. Applekamp 10-18-95  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4"x96" aluminum rod with a 3/4" cap  
stamped to read: COUNTY REMONUMENTATION, T48N R42W,  $\frac{1}{4}$ , S.6, S.7,  
1995, P.S. 17610. I established the following bearing trees and  
reference objects:

4" Maple S63°W 38.50 feet - 1 1/2" Maple S32°E 12.27 feet  
3" Maple N43°W 22.50 feet - Steel Sign Post, North 1.52 feet



Signed by Earl W. Applekamp

Date October 06, 1995

Surveyor's Michigan License No. 17610