

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. 51 N. R. 40 E. W.		I-12, I-13, J-11
2. PROPERTY CONTROLLING IN SECTION_____ T. _____ S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION_____ T. _____ S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I-12: Original monument and accessories not found. Found old squared up post.

Corner I-13: Original monument and accessories not found.

Corner J-11: Original monument and accessories not found. Found old north-south-east fence corner which has been used as corner for many years.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I-12: Found old squared up post and blazes in area. Re-established 9-8-76 at post. Pits good with section corners north and south.

Corner I-13: Re-established 9-8-76 on line between section corners east and west.

Corner J-11: Re-established 11-4-76 at fence corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-12: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

5" Maple S58°W 8.9 ft. 1/4S, NBT
6" Maple S80°E 4.0 ft. 1/4S, NBT
8" Maple N14°W 29.7 ft. 1/4S, NBT

Corner J-11: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

4" Maple S70°W 63.9 ft. 1/4S, NBT
6" Ash N10°W 59.6 ft. 1/4S, NBT

Corner I-13: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

4" Ash S57°E 14.7 ft. S 6, NBT
7" Maple N74°W 35.5 ft. S34, NBT
9" Aspen N71°E 25.2 ft. S35, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Michael W. Roose Michael W. Roose DATE 12/28/76

APPROVED AND SIGNED BY Keith L. Sackett DATE 12/28/76
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1973

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET