

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ontonagon  
(County) Located In: Corner Code #

1. Public Land Survey T 51N R 41W K-6  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Section S T R

4. Lot No. , Recorded Plat  
5. Private Claims

SURVEY &  
REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

One-quarter section corner common to Sections 13 and 14, T51N, R41W.

I, John R. Garske, in a field survey on July 17, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In April 1846, S.W. Higgins, U.S. Deputy Surveyor, set a post with the following bearing trees:  
18" Hemlock - S35°W - 23 links  
30" DO - N31°E - 50 links

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set the corner at the intersection of an ancient fence line intersection running north, south and east. This location is consistent with natural feature ties and is generally considered to be the one-quarter corner.

Record research on file.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3' x 3/4" aluminum rod with a 3 1/4" aluminum cap stamped: County Remonumentation, T51N, R41W, 1/4, S-14, S-13, 1996, R.L.S., 28410. The following bearing trees and reference objects were established:

- 6" steel sign rail - S40°E - 1.41 feet  
12" twin maple - N50°W - 8.54 feet  
4" Y. birch - N45°E - 2.64 feet  
9" H. maple - S12°W - 23.79 feet

Bearing trees were blazed and painted.

PEER GROUP ATTORNEY  
Earl W. Applekamp  
COUNTY REPRESENTATIVE  
8-14-96



Signed by

John R. Garske

Date

8-14-96

Surveyor's Michigan License No. 28410