

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 29 1999

For corners in

Presque Isle
(County)

Located in:

Corner Code #

SECTION

PRESQUE ISLE COUNTY
RECORDED

1999 DEC -2 PM 2:14

Eric M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey

T 34 R 4 E

B-13

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Delmer E. Porter in a field survey on Nov. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13 GLO Notes - 1856

Set 1/4 Section Post

24" Pine N31° E 18 Lks

8" Pine N62° W 17 Lks

R. Bischer #22428, L 1, Pg 606, 1" Pipe

S32° 30' E 79.70' 8" Aspen

N59° 30' E 77.50' 7" Aspen

N81° 30' W 75.64' 8" Pine Stump


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 Found 1" Pipe

S32° E 79.90' 19" Poplar Stump

N64° E 77.50' Stump

N81° W 75.00' Burnt Blazed Stump



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 1" Pipe

N81° W 75.00' Burnt Blazed Stump

N25° E 10.40' Burnt Blazed Stump

N64° E 77.50' Stump

S45° E 44.80' 10" Norway

S32° E 79.90' 19" Poplar Stump

S25° E 37.22' Burnt Blazed Stump

*Witness tags & nails used.

Qualified by Peer Group
in accordance with P.A. 345Chairman *Norman J. Quinn*Date 11/30/99Signed by *Delmer E. Porter*
Surveyor's Michigan License No. #15410Date 11-15-99