

#1057

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Presque Isle Located In: Corner Code #
(County)

- 1. Public Land Survey T 34N R 5E E-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

PRESQUE ISLE COUNTY
RECORDED

95 JUN 13 PM 12:22

Janet M. Lamb

REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Ronald Bischer, in a field survey on 3-29, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-7
1856 Alfred Millend Set Wood Post
N50°E 24 links 24" Sugar
S40°W 28 links 15" Hemlock
4-4-78 Delmar Porter Fd. Nail (Farrier 1976), set 1/2" rod in Mon. box
left 3 witnesses
6-14-89 Duane MacNeill Found Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-7
3-29-96 Ronald Bischer found 1/2" Rod & Cap #15410 in Mon. box
N69°E 91.10' 10" Ash
S49°W 51.28' P. pole



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-7
3-29-96 Ronald Bischer
1/2" Rod & Cap #15410 in Mon. Box
N69°E 90.80' 18" Ash
S49°W 51.96' P. pole
N39°E 58.90' P. pole
N14°W 116.48' Tele. Cable Box

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmar Porter*
Date 6/12/96

Signed by Ronald R. Bischer

Date 6-6-96

Surveyor's Michigan License No. 22428