

SURVEY &
REMONUMENTATION

8345

APR 24 1995

ROSCOMMON COUNTY REMONUMENTATION TO BE FILED IN LIBER 3 OF LAND CORNERS

LAND CORNER RECORDATION CERTIFICATE

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 22N, R 2W	A-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

14 NOV 94 3:06 P.M.

ROBERT U. SMITH
REGISTER OF DEEDS

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 10-20-94

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|--|--|--------------------|
| Post set by John Burt 1838 | 1980 Survey L. Cavanagh P.S. | 1982 Norman Parker |
| Cedar 10" S5 1.2°W 22 links | Found 1/2" Bar | |
| Birch 9" N49 1/2°W 37 links | SE Cor Sec. 24 | |
| | Nail and tag N. face 8" poplar S75°E 51.08' | |
| 1929 DeLaMater | Nail and tag SE face 12" Oak N73°E 23.02' | |
| Found both Government bearing trees and post | 24" W Pine N5°W 23.2' | |
| Set 1/2" x 30" iron | Nail and tag N. face 18" W. Pine S80°W 55.19 | |
| N.B.T. | 1980 Cavanagh, LCRC Liber 1, Page 196 | |
| Y. Pine 8" N65°W 68.0' | Same Witnesses | |
| W. Pine 10" S50°E 82.6' | | |
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 1/2" bar as called for in previous surveys
- 1992 Larry Cavanagh found 1/2" bar as previously called for with all accessories, except 8" poplar

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 1/2" x 24" cast iron Roscommon County Monument
17614 - 1994
S50°W nail and tag in 5" W. Pine 27.34'
S38°E nail and tag in 5" Maple 25.04'
N5°W nail and tag in 24" W. Pine 24.18'
N65°E nail and tag in 16" W. Oak 22.67'
N12°E Carsonite post 1.33'

Is accepted as a perpetuation of the original government corner.

Signed by


Larry L. Cavanagh

Date

11/19/94

Surveyor's Michigan License No.

17614



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 126