

SURVEY & REMONUMENTATION

APR 07 1998

9201 SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22NR 3W	C-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 10:09 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS
FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on September 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1849
William A. Burt, D.S.
Mon: Maple Post
Wit: 30" Red Oak N65° W 17 links
24" Red Oak S60°E 45 links

Liber 2, Page 234
Mon: Iron rod 7.4 East of Centerline

Larry L. Cavanagh, R.L.S. 17614
L. 352, P. 504, 31, August 1978
Mon: No description provided
Wit: 24" Oak N19°E 68.89'
23" Oak S42°E 56.98

Robert t. Ostling R.L.S. # 5133
Unrecorded Survey 12 August 1964
Mon: No description provided
Wit: No witnesses provided

Larry L. Cavanagh, R.L.S. #17614
L. 1, P. 124, 18, January 1979
Mon: 1/2" bar in Pav't Box
Wit: 24" Oak N19°E 68.89'
23" Oak S42°E 56.98

C. Eugene Ostling R.L.S. # 12026
Unrecord Survey 7, August 1968
Mon: No description provided
Wit: No witnesses provided

Larry L. Cavanagh, R.L.S. #17614
L. 1, P. 269, 14 February 1990
Mon: Iron in pav't box
Wit: 24" Oak N19°E 68.89'
23" Oak S42°E 56.98
4" Oak N20°E 62.1
18" Oak S72°W 65.3

Larry L. Cavanagh, R. L.S. 17614
L. 1, P. 191, 27, July 1980
Mon: 3/4" Iron
Wit: 4" Oak N20°E 62.1
18" Oak S72°W 65.3
Conc. Mon. East 33.00
6" Red Oak N80°W 47.53

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 3/4" Iron in water valve box. Found 26" Oak stump S72°W 65.3': Found Oak Stump hole S42°E 56.98': Found concrete monument East 33.22': Found 8" Red Oak with blaze N80°W 47.2
Accepted 3/4" Iron as the best available evidence of the position of the Original Government corner.
Replaced pipe with Standard Roscommon County monument placed in new standard pavement box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Roscommon County Monument in Pavement box.
Set Nail & tag in NE side 5" White Pine N64°W 44.44'
Nail & tag in SE side 7" Oak 215° 15.66'
Set Nail & tag in South side 2" Poplar 313° 23.14'
Set Nail & tag in West side 3" Oak 347° 11.39'
Set Nail & tag in South side 4" Maple in clump 31

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE DEC 5, 1997

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600



Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1971
REVISED JAN., 1997

LIBER 3 PAGE 435