

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Sanilac COMMISSION  
(County)

Located in: Corner Code -#

- 1. Public Land Survey T 11N R 15E H - 13, G - 13  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

RECEIVED FOR RECORD

93 DEC 29 AM 10:55

LIBER 1 PAGE NO. 432  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A. Milletics, in a field survey on Oct 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H - 13

Found 1/2" iron bar in gravel Road Bed, per survey dated 7-13-84 showing iron set over plow point

G - 13

Found 5/8" iron bar in gravel road bed, per Irvin E Chope Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 13

S 1/4 Cor Section 34 T11N-R15E  
Found 1/2" iron bar

G - 13

SW Cor Section 34 T11N-R15E  
Found 5/8" iron bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H - 13

S 1/4 Cor Section 34 T11N-R15E  
1/2" iron bar  
North 35.55' to a nail in a 18" Maple  
N50°W 72.10' to a nail in a 12" Ash  
N70°E 56.70' to a nail in a 10" Ash  
East 2670.64' to the SE Cor Section 34

G - 13

SW Cor Section 34 T11N-R15E  
5/8" iron bar  
N45°W 39.95' to a Stop Sign  
S30°W 19.35' to the East Leg of a Road Sign  
N45°W 40.00' to the North End of a 12" CMP  
S45°W 40.30' to the South End of a 12" CMP

Signed by John A. Milletics

Date Dec 24, 1993

Surveyor's Michigan License No. 25859