

MAY 05 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 118

For corners in

ST. JOSEPH
(County)

Located In:

Corner Code #

MENDON TWP.

1. Public Land Survey

T 5S R 10W

E-11

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

11 APR 95 2:12 P.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, WAYNE A. MOSTROM in a field survey on MARCH 31, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11 1864 SURVEY BY GARDNERSURR. COR'S SET BUT NOTHING
ON E-111903 SURVEY BY TODD

FOUND STONE IN PLACE

28" RED OAK = N76 3/4°E

1.95 CH.

ROAD COMMISSION (FROM SAYERS NOTES) & LCRC IN 3/18

STONE IN MON. BOX 20" OSAGE ORANGE = NW 50.9'

24" CHERRY = NE 26.33'

20" TREE = SE 53.00'

1976 SURVEY BY MOSTROM SHOWS IRON 33'E.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD/ 3/4" PIPE OVER STONE 15" DEEP IN MON. BOX

BENT IRON = 33' EAST

NOTE: RDWY. HAS BEEN IMPROVED

COR. IS IN CL OF N-S RDWY & IN EXTENSION OF GRAVEL RDWY TO WEST.

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON April 18, 1995
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 SET 5/8" X 24" IRON BAR WITH STD. CAP OVER STONE
IN MON. BOX

N & W IN WEST SIDE POWER POLE = S15°E 115.57'

N & W IN SW SIDE 14" OAK = S58°E 74.55'

N & W IN S. SIDE 12" OAK = S80°E 61.74'

N & W IN NW SIDE 10" WAL. = N36°E 67.50'

NOTE: PK'S & WASHERS ARE 24" ABOVE GRADE



Signed by

Date

4/11/95

Surveyor's Michigan License No.

14100