

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

FEB 08 2001

DATE 10/10/00 JCB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

SIGRID HEDBERG

1P

SCHOOLCRAFT CO. REGISTER

Page 1 of 1

LC 4/366

JLV Date 12/19/2000

Time 11:53:15

1. Public Land Survey

T42N R 14W

K4

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/17/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 7, 1851 Algernon Merryweather, DS set $\frac{1}{4}$ post Ironwood 9 in N15W 19 links
Sugar 10 in S20E 53 links

March, 1984 William F. Bowman, LLS "set by evidence of road location, old fence lines and corners $\frac{1}{2}$ mile North and $2\frac{1}{2}$ miles South."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 17, 2000 Thomas P. O'Brien, PS found P.K. from 1998-99 corner preservation resurface project. Reset with $\frac{1}{2}$ " iron bar with OBRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

$\frac{1}{2}$ " iron bar with OBRIEN 21274 cap in monument box.

Witnesses:


Power Pole N46°W 41.32'

NW corner culvert abutment S54°E 26.10'

NE corner culvert abutment S65°W 24.70'

Carsonite post S85°E 30.0'

Corner falls in N and S centerline.



Signed by Thomas P. O'Brien

Date Dec. 18, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 366