

# SCHOOLCRAFT COUNTY PEER GROUP APPROVED

SURVEY &  
REMONUMENTATION

JAN 21 1998

DATE 10/15/97

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft  
(County)

Located In:

Corner Code #

1. Public Land Survey

T42NR16W

G-7

2. Property Controlling  
in Section

S

T R  
T R  
T R  
T R  
T R  
T R

3. Miscellaneous  
Property in Sec.

S

S

T R  
T R  
T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SECTION

Received & Filed this 9 day of  
Dec 1997 at 3:46 P M  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

I, Thomas P. O'Brien, in a field survey on Nov. 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7 NW Corner Section 22

Aug. 14, 1850 - Algernon Merryweather D.S. set corner post.  
Tamarack 6 N85E 8 lks. Willow 5 S51W 23 lks.

May 25, 1950 - Carl Christensen set corner from original B.T.'s as noted in County Surveyors Record page 119.

Feb. 20, 1957 - Billy D. Buckler R.L.S. recovered a 2" iron pipe w/brass cap and Tam. B.T. S56W 22lks. in fair cond. LCRC recorded Liber 3, page 182.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Feb. 7, 1977 - Beryl M. Jones R.L.S. "Fd. pipe & brass cap LCRC recorded Liber 1, page 236.

G-7 Nov. 7, 1997 - Thomas P. O'Brien P.S. recovered a 2" iron pipe with brass cap stamped with section numbers and initials "C.C."  
Witnesses found verify corner location as set by Carl Christensen.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 2" iron pipe with brass cap stamped with section numbers and initials "C.C."


Witnesses:

(Fd.) 5" Cedar - N77°E - 7.76'  
(Fd.) 8" Cedar - S61°W - 28 lks. (Down)  
(Fd.) 8" Cedar - N72°W - 32 lks. (Down)  
NBT 5" Cedar - South - 37.64'  
NBT 8" Cedar - S80°W - 25.15'  
NBT 6" Cedar - N18°W - 7.08'  
4" Cedar Post - North - 2.0'

Signed by Thomas P. O'Brien P.S.

Surveyor's Michigan License No. 21274

Date November 26, 1997



LIBER 4 PAGE: 127