

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED
DATE 10/15/97

SURVEY &
REMONUMENTATION

JAN 21 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft
(County)

Located in:

Corner Code #

1. Public Land Survey

T42NR16W

I-11

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Thomas P.O'Brien, in a field survey on Oct. 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Received & Filed this 23 day of
Dec 1997 at 3:07 PM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | X | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

I-11 NW corner Section 35

Aug. 13, 1850 - Algernon Merryweather D.S. set corner post.
Birch 24 in. N70E 33 lks. do. 18 in. S59W 48 lks.

June 5, 1975 - Thomas P.O'Brien P.S. "found 1/2" bar @ road intersection
E + W, N. LCRC recorded Liber 1, page 158.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Oct. 31, 1997 - Thomas P. O'Brien P.S. found hole in black top, at
intersection of East + West, North roads. Hole matches B.T. distances,
as found on June 5, 1975. Set I.B. with O'Brien cap #21274 in
monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 1/2" Iron bar with O'Brien cap # 21274 in monument box.

Witnesses: (Fd.) 28" W. Pine - N48°E - 57.05'
(Fd.) 24" Maple - N15°W - 58.65'
NBT 12" W. Pine - S43°E - 66.86'
NBT 12" W. Pine - S74°W - 90.36'
4" Cedar Post - South - 30.0'



Signed by Thomas P. O'Brien P.S.

Date November 28, 1997

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 153