

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 15W T 43N R 15W T _____ R _____	E5 F5 _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	_____ _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 03/14/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E5) Corner common to Sections 8-9-16-17. 1972 - F.J.Bray RLS reestablished the corner position by double proportionate measurement between corners 1 mile north, 2 miles east, 1.5 mile south, and 1/2 mile west. Set 1"ID Iron pipe with 4" alum. cap. 7" R.Pine N81E 50.7', 8" J.Pine N68W 23.1'.

(F5) Quarter corner common to Sections 9-16. 1972 - F.J.Bray RLS reestablished the corner position midway and on the Section line between Section corners 1/2 mile east and west. Set 1"ID I.pipe with 4" alum. cap. 14" R.Pine N75E 25.2', 12" W.Pine S11W 12.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E5) Found the 1972 monument disturbed, the top portion bent. The lower portion of the monument was recovered plumb, in good condition, and at record bearing and distance from the remaining 1972 witness R.Pine, 16", found N84E, 50.7' distant, in good condition with open blazes. Accepted the position as a careful and faithful reestablishment of the position of the original corner and replaced the 1972 monument with a new monument, described below.

(F5) Found the 1972 monument in good condition and at substantial record bearing and distance from the 1972 witnesses, both in good condition. Accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E5) Set 1"IDx36" I.pipe with MDNR plastic cap. Set measuring nail with MDNR tag in the side of: 16" R.Pine N84E 51.0' old blazes 1972 NBT 8" R.Pine S62W 32.3' mrkd "S17 NBT" 7" Balsam S81W 3.9' do 7" J.Pine N51W 19.65' "S8 NBT" Bearings are magnetic.

(F5) Fd. 1"ID I. pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of: 16" R.Pine N76E 25.2' mrkd "1/4S" 1972 NBT 14" W.Pine S18W 11.4' do do 10" R.Pine N20E 24.5' "1/4S NBT" 10" J.Pine S50W 16.2' do Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/06/2012

For the Michigan Department of Natural Resources, Forest Resources Division

