

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 15W	H5
	T R	
	T R	
2. Property Controlling in Section	S 15 T 43N R 15W	1
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/15/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 15) West 1/16 corner between Sections 10 and 15. 1972 - F.J.Bray intended to monument the position midway and on the Section line between G5 and H5. Set 1"ID iron pipe with MI Dept. of Conservation cap. 4" R.Pine N86°W 27.7', 3" W.Pine S18°E 15.7'

(H5) Quarter corner common to Sections 10 and 15. 1972 - F.J.Bray intended to monument the position midway and on the Section line between Section corners G5 and I5. Set 1"ID iron pipe with MI Dept. of Conservation cap. 11" H.Maple N48°W 24.2', 12" H.Maple S11°E 13.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 15) Found the 1972 monument in good condition 16.98' south of the position subsequently monumented. I determined that the 1972 Bray survey suffered from a blunder which caused him to monument corners #1, H5, and #2 in Sec. 15 too far south. I established the position for the corner midway and on the Section line between Section corner 1321.12' west and Quarter corner 1321.12' east. Removed the 1972 monument and drove it at said position.

(H5) Found the 1972 monument in good condition 33.89' south of the position subsequently monumented. I determined that the 1972 Bray survey suffered from a blunder which caused him to monument corners #1, H5, and #2 in Sec. 15 too far south. I established the position for the corner midway and on the Section line between Section corners 2642.24' east and west. Removed the 1972 monument and drove it at said position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1"ID I.pipe with 4" MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of: 12" W.Pine S72°E 11.55' 14" W.Pine S03°E 32.0' 18" W.Pine S64°W 32.45' 12" W.Pine N04°W 23.3' Set sq'd pine post adjacent. E= 8063921.231 N= 149884.591	(H5) Set 1"ID I.pipe with 4" MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of: 22" Maple N50°W 8.2' 6" Maple S48°W 12.15' 16" Sugar S01°W 47.65' 4" Sugar S41°E 13.9' Set sq'd pine post adjacent. E= 8064323.788 N= 149892.164
---	--

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Coord. Ref.=NGS PID DL6164: N= 131822.939 m. E= 8059239.498 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/25/2013

For the Michigan Department of Natural Resources, Forest Resources Division

