

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T46&47NR 13 W ..

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 6 and 31. -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 36" W. Pine Stump N 31° E 88 links -----


DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Corner established by proportionate measure by Survey Crew.

No original evidence.

Corner placed 9 links West and 37 1/2 links South of 37.42 ch. from West.

Corner placed and witnessed June 24, 1955.



SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/28/56
REGISTERED LAND SURVEYOR