

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 14W	H1
	T 46N R 14W	J3
2. Property Controlling in Section	T R	
	T R	
	T R	
3. Miscellaneous Property in Sec.	T R	
	T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on H1 04/12/2010 J3 04/19/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H1) Quarter corner common to Section 3 T46N-R14W and Section 34 T47N-R14W. 1841 - Established by Wm.Burt Deputy Surveyor. Set post. W.Birch 8" N45E 24 links, Y.Pine 11" N41W 35 links. 1953 - Remonumented by D.C.DeLaMater RLS at record bearing and distance from original B.T., still in place, in poor condition. Set 1"ID I.pipe with 4" brass cap. 12" R.Pine N72E 131 links, 12" Red Pine S54W 133 links.

(J3) Quarter corner common to Sections 2 and 11. 1960 - Remonumented by Billy D. Buckler RLS from W.Pine B.T. N10W 72 links, down and in poor condition. Set 1" pipe with 4" brass cap. 10" R.Pine N10W 82 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H1) Found the 1953 monument in good condition and at record bearing and distance from the 1953 NBTs, in good condition. Also at record bearing and distance the Y.Pine B.T. N41W 35 links, now a stump with blaze visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(J3) Found the 1960 monument in good condition and at record bearing and distance from the 1960 R.Pine NBT, now 16" DBH, in good condition with overgrown blazes. The B.T. W.Pine N10W 72 links noted in Mr. Buckler's record was not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H1) Fd. 1"ID I.pipe with 4" brass cap.
Set measuring nail with MDNR tag in the side of:
14" R.Pine S59W 88.5' mrkd "1/4S" 1953 NBT
10" R.Pine S06W 14.75' "1/4S NBT"
5" Maple N13E 11.75' do
10" R.Pine N77W 19.3' do
Bearings are magnetic.

(J3) Fd. 1"ID I.pipe with 4" brass cap.
Set measuring nail with MDNR tag in the side of:
16" R.Pine N06W 54.65' mrkd "1/4S" 1960 NBT
4" Maple S55W 49.45' "1/4S NBT"
20" W.Pine N77W 42.45' do
12" W.Pine S86E 70.0' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/01/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

