

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 14W	H3
	T R	
	T R	
2. Property Controlling in Section	S 3 T 46N R 14W	12
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3								10		11		12	
4	7		8		9								
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on H3 04/28/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H3) Quarter corner common to Sections 3 and 10. 1850 - Established by Guy Carleton Deputy Surveyor. Set post. Y.Pine 16 S43W 31 links, Y.Pine 18 N65E 28 links. 1960 - Remonumented by Billy D. Buckler RLS "from two Yellow Pine stumps (probable B.T.s)...Found a discolored streak in soil at corner which could have been caused by a rotting wood stake". Set 1" pipe with 4" brass cap. 14" R.Pine S25E 111 links, 15" R.Pine N83W 107 links.

(12-Sec. 3) South 1/16 corner, Section 3. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H3) Found the 1960 monument in good condition and at record bearing and distance from the 1960 NBTs. The R.Pine NW is in good condition. The R.Pine SE is a stump. Found stump remains of original B.T. Y.Pine S43W 31 links at record bearing and distance. The other orig. B.T. was not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(12-Sec. 3) Established the corner midway and on a straight line between Center of Section 1336.68' north and Quarter corner 1336.68' south. The position for the corner falls in the Fox River and was not monumented. Set a Witness Corner 50.00' westerly from the 1/16 corner position and on the South 1/16 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H3) Fd. 1"ID I.pipe with 4" brass cap.
Set measuring nail with MDNR tag in the side of:
21" R.Pine N77W 71.4' mrkd "1/4S" 1960 NBT
10" twin R.Pine N20W 105.85' mrkd "1/4S NBT"
17" R.Pine N22W 89.35' do
5" J.Pine N86E 88.95' do
Bearings are magnetic.

(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap, appropriately stamped, as a witness corner 50.00' west of the corner position and on the 1/16 line. Set nail with MDNR tag in the side of:
9" Maple S85E 14.35' mrkd "WC BT"
10" Cherry S33W 30.2' do
20" R.Pine West 20.8' do
20" R.Pine N30W 34.25' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/01/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

