

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 14W T 46N R 14W T R	I4 G1
2. Property Controlling in Section	S T R S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on I4 04/05/2010  
G1 04/29/2010 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I4) Quarter corner common to Sections 10 and 11. 1850 - Established by Guy Carleton Deputy  
Surveyor. Set post. Y.Pine 24" N80E 17 links, W.Pine 20" N23W 24 links. 1956 - Billy D. Buckler  
RLS remonumented the corner from two Pine B.T.'s in good condition. Set 1" pipe with 4" brass cap.  
12" R.Pine S85E 176 links, 22" Red Pine Stp. N06E 70.5 links.

(G1) Corner common to Sections 3-4 T46N-R14W and Sections 33-34 T47N-R14W. 1953 - D.C.DeLaMater RLS  
reestablished the corner position by proportionate measurement. No original evidence at corner. Set  
1"ID I.pipe with 4" brass cap. 30" W.Pine stump N05E 15 links, 36" W.Pine stump S47W 112 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I4) Found the 1956 monument in good condition and at record bearing and distance from the remains of  
the original B.T.s Y.Pine and W.Pine, now both stumps with traces of blaze visible. Also at record  
bearing and distance the 1956 NBTs R.Pine SE, in good condition and the stump R.Pine NE. Accepted  
the monument as a careful and faithful perpetuation of the position of the original corner.

(G1) Found the 1953 monument in good condition and at record bearing and distance from the 1953  
W.Pine stump witnesses. Accepted the monument as a careful and faithful reestablishment of the  
position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I4) Fd. 1"I.pipe with 4" brass cap.  
Set measuring nail with MDNR tag in the side of:  
4" R.Pine S31E 52.7' mrkd "1/4S NBT"  
9" J.Pine N85E 34.75' do  
6" J.Pine N35E 49.05' do  
3" J.Pine S72W 18.95' do  
Bearings are magnetic.

(G1) Fd. 1"ID I.pipe with 4" brass cap.  
Set measuring nail with MDNR tag in the side of:  
10" R.Pine N61E 31.3' mrkd "S34 NBT"  
14" R.Pine N07W 10.6' "S33 NBT"  
6" Maple in clump N78W 14.5' do  
12" R.Pine S55E 61.6' "S3 NBT"  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/01/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division



47429

47432