

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 14W

J5

T R

T R

S T R

2. Property Controlling
in Section

S 14 T 46N R 14W

1

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Oct 02 2003

I, Stephan J. Szyszkoski

, in a field survey on , 20 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J5) Quarter corner common to Sections 11-14. 1962: Billy D. Buckler RLS reestablished the corner midway and on line between section corners. Set 1" pipe with 4" aluminum cap. 7" Jack Pine S65E 63 links, 9" Jack Pine N49E 56 links.

(1-Sec. 14) West 1/16 corner between Sections 11-14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) Recovered the 1962 monument in good condition and at record bearing and distance from the 1962 witnesses. The 1962 position for the corner is not accepted due to the reestablishment by the undersigned of the Section corners I5 and K5, upon which the location of this corner depends. Reestablished the corner midway and on a line of mean true bearing between these two Section corners, which are 2618.16' West and East. From the corner thus established, the 1962 position, now destroyed, is S80W 49.63' distant. Found no evidence of the original 1850 bearing trees. The 1962 MBTs were used as new witnesses, as described below. Relocated the 1962 monument to the corner position.

(1-Sec. 14) Established the corner midway and on a line of mean true bearing between Section corner 1309.08' West and Quarter corner 1309.08' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Set 1" 10x36" I.pipe with 4" brass

MDNR cap. Blazed, scribed, and set

measuring nails in:

10" W.Pine N20E 36.7' "1/4S MBT"

12" W.Pine N58E 29.45' do

12" J.Pine N47W 26.95' do

10" J.Pine S27W 24.35' do

Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(1) Set 1" 10x36" I.pipe with 4" aluminum

MDNR cap. Blazed, scribed, and set

measuring nails in:

5" Spruce N62W 10.25' "W1/16 BT"

10" J.Pine N23W 21.85' do

8" J.Pine S85E 18.65' do

6" J.Pine S25W 21.7' do

Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

11/18/03

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995