

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| Schoolcraft<br>(County)               | Located in: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey                 | T 46N R 14W | K6            |
|                                       | T 46N R 14W | L6            |
|                                       | T R         |               |
| 2. Property Controlling<br>in Section | S T R       |               |
|                                       | S T R       |               |
| 3. Miscellaneous<br>Property in Sec.  | S T R       |               |
|                                       | S T R       |               |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims

L6 Sep 29 2003  
K6 Sep 30 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K6) Quarter corner common to Sections 13-14. 1962: Billy D. Buckler RLS reestablished the corner midway and on line between Section corners. Set 1"IDx36" I.pipe with 4" Aluminum cap. 7" Jack Pine S51W 18 links, 8" Jack Pine N19E 56 links.  
(L6) Center of Section 13. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K6) Recovered the 1962 monument in good condition and at record bearing and distance from the remaining witness J.Pine SW, now dead and down. The 1962 position for this corner is not accepted due to the reestablishment by the undersigned of the Section corners K5 and K7, upon which the position of K6 depends. Reestablished the corner midway and on a straight line between K5 and K7 2652.35' North and South. I destroyed the 1962 corner which was S78W 60.14' from the position described herein. The bearing trees from the original 1850 survey by Guy Carleton were not found. From the corner thus established, found a "t"-type iron fence post S83W 59.14'.  
(L6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

|   |   |
|---|---|
| (K6) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Blazed, scribed, and set<br>measuring nails in: | (L6) Set a 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Blazed, scribed, and set<br>measuring nails in: |
| 6" J.Pine N30W 21.5' "1/4S NBT"   | 14" W.Pine N22E 1.4' "CS 8T"  |
| 8" J.Pine N86E 8.95' do   | 12" J.Pine S16E 16.8' do  |
| 6" J.Pine S36W 43.6' do   | 10" J.Pine N76W 38.6' do  |
| 5" J.Pine S22E 26.55' do  | 8" J.Pine N40W 22.2' do   |
| Placed a cedar post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag.          | Placed a cedar post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag.            |



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 11/18/03

For the Michigan Department of Natural Resources, Office of Land and Facilities