

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 15W	D9
	T 46N R 15W	C8
	T	
2. Property Controlling in Section	S T	
	S T	
	S T	
3. Miscellaneous Property in Sec.	S T	
	S T	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on D9 02/24/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D9) Quarter corner common to Sections 20 and 29. 1850 - Established by Guy Carleton Deputy Surveyor
midway and on the Section line between Section corners 40.25 chains east and west. Set post. Cedar
5" N24E 10 links, Cedar 6" S10W 6 links.

(C8) Quarter corner common to Sections 19 and 20. 1961 - Reestablished by single proportionate
measurement to the original record by Billy D. Buckler RLS. Set 1" iron pipe with 4" brass cap. 16"
Tamarack N67E 82 links, 12" Cedar S29E 87 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D9) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the position for the corner midway and on the Section
line between Section corners 2661.39' east and west.

(C8) Found the 1961 monument in good condition and at record bearing and distance from the 1961
witnesses. The Cedar SE is in good condition, the Tamarack NE is standing dead. Found the monument
to be substantially at the record position between Section corners and accepted same as a careful and
faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" Cedar S23W 21.05' mrkd "1/4S NBT"
5" B.Spruce S74W 6.3' do
6" W.Birch N27W 4.4' do
6" W.Birch S86E 4.65' do
Bearings are magnetic.

(C8) Fd. 1"ID I.pipe with 4" brass MI Dept of
Conservation cap. Set measuring nail with
MDNR tag in the side of:
5" B.Spruce N84E 17.55' mrkd "1/4S NBT"
14" Tamarack S27W 65.4' do
8" Tamarack N01E 39.2' do
13" Cedar S25E 57.9' open blaze
Bearings are magnetic.

Signed by

Stephan J. Szyszkoski

Date

05/05/2011

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities



47476

47477

FORM APPROVED BY MICHIGAN STATE BOARD

1971
14, 1975
Jan., 1983
Revised Oct., 1995