

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 15W

H1

T 46N R 15W

I1

T R

S T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I1 Jun 07 2006

H1 Mar 15 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H1) Quarter corner common to Section 3 T46N-R15W and Section 34 T47N-R15W. 1964 - Reestablished by single proportionate measurement to the original record by Frank J. Bray RLS. Set 1" Iron pipe with 4" aluminum cap. 7" Tamarack N33W 122 links, 22" W.Pine S75E 139 links.

(I1) Corner common to Sections 2-3 T46N-R15W and Sections 34-35 T47N-R15W. 1963 - Remonumented from the remains of two original Cedar BTs by Billy D. Buckler RLS. Set 1" pipe with 4" aluminum cap. 10" Tamarack S44E 49.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H1) Recovered the 1964 monument in good condition and at record bearing and distance from the 1964 accessories, both in good condition. My measurements show this monument is located 0.62' from the proportionate position intended in 1964 and I accept the monument as a careful and faithful reestablishment of the position of the original corner.

(I1) Recovered the 1963 monument in good condition and at record bearing and distance from the 1963 NBT Tamarack, now standing dead. the original Cedar BTs are now gone. Made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H1) Fd. 1" I.pipe with 4" alum. MI
Dept. of Conservation cap. Set
measuring nails in:
13" Tamarack N31W 81.1' mrkd "1/4S" *
24" W.Pine S72E 92.95' do *
12" W.Pine N40W 15.65' mrkd "1/4S NBT"
6" Tamarack S19W 22.6' do
Bearings are magnetic. Distances are to
nail with tag. * denotes 1964 NBT.

(I1) Fd. 1" I.pipe with 4" alum. MI Dept.
of Conservation cap. Set measuring
nails in:
18" Cedar S41E 33.85' mrkd "S2 NBT"
5" Cherry S79E 12.5' do
14" Balsam S10E 19.65' do
18" Spruce N55W 54.0' "S34 NBT"
Bearings are magnetic. Distances are to
nail with tag.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

8/15/06

For the Michigan Department of Natural Resources, Office of Land and Facilities