

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

1. Public Land Survey T46N R 15W I10
T R
T R
S T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski , in a field survey on Sept. 25 , 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(I10) Quarter corner common to Sections 26 and 27. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.125 chains north and south. Set post. Tamarack 6 N84W 21 links, Tamarac 8 S84E 13 links. 1960 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" pipe with 4" brass cap. 12" power pole S19E 38 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(I10) The original post and accessories were not recovered. The 1960 monument was recovered out of position, disturbed, bent, and with cap missing. The power pole witness was recovered but not deemed to be sufficient to remonument the corner with certainty. Reestablished the corner midway and on the Section line between Section corners 2652.76' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(I10) Set 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nails with MDNR tags in the sides of the following 3 objects:
6" Tamarack S35W 67.05' mrkd "1/4S NBT"
7" Tamarack S76W 114.8' do
P.Pole S33E 11.43'
1" pipe N6E 15.31'
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS