

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 16W	D5
	T R	
	T R	
2. Property Controlling in Section	S 8 T 46N R 16W	16
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 06/12/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D5) Quarter corner common to Sections 8 and 17. 1963 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. No original evidence found. Set 1" iron pipe with 4" aluminum cap. 8" W.Pine N76°W 198 links, 7" W.Pine S35°E 238.5 links.

(16-Sec. 8) East 1/16 corner between Sections 8 and 17. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D5) The 1963 monument was recovered disturbed and out of position. Due to the systematic and random errors present in the 1963 survey and the positional uncertainty which would result in the reestablishment of the 1963 position from such distant witnesses, I chose to reestablish the corner position according to the method employed in 1963. Therefore, I remonumented the corner position midway and on the Section line between Section corners 2642.54 feet east and west.

(16-Sec.8) Established the position for the corner midway and on the Section line between Quarter corner 1321.27' west and Section corner 1321.27' east. From the position thus established, I found a 1"ID iron pipe with an MI Dept. of Conservation cap, not stamped to identify, not of record, SE 6.5' distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D5)Set 1"ID iron pipe with 4" MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
6" Tamarack N84°E 73.0' mrkd "1/4S NBT"  
12" W.Pine S44°E 79.35' do  
10" W.Pine S29°W 73.7' do  
8" W.Pine S07°E distance lost do  
4" W.Pine post adjacent.  
E= 8051155.972 N= 178779.954

(16) Set 1"ID iron pipe with 4" MI Dept. of Conservation cap, stamped to identify the corner. Set measuring nail with MDNR tag in the side of:  
20" twin Sugar N04°W 6.4' mrkd "E1/16 BT"  
14" Sugar S72°W 23.45' do  
14" Hemlock East 42.0' do  
12" Hemlock N40°W 49.25' do  
E= 8051558.639 N= 178781.239

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).  
Coord. Ref.=NGS PID RK0046: N= 173923.068 m. E= 8052746.340 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/10/2013

For the Michigan Department of Natural Resources, Forest Resources Division

