

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.47.. NR. 13.W..

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 26 and 27 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 24" W. Pine Stump N 4° E 83 links -----

30" W. Pine Stump N 75° E 121 links -----


DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Corner established by crew. No original evidence.

Corner falls in old railroad grade.

Corner placed 2 links North and 1/2 link East of 39.90 marker from South.

Corner placed and witnessed June 16, 1955.



SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 2/28/56
REGISTERED LAND SURVEYOR