

SURVEY & REMONUMENTATION

NOV 10 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 NOV -6 PM 2:37

REGISTER OF DEEDS

Hayes Mullett
SHIAWASSEE COUNTY, MICH.

For corners in

Shiawassee
(County)

Located in:

Corner Code #

1. Public Land Survey

T 6N R 2E M-10

T R

T R

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

Mark L. VanRaemdonck, in a filed survey on June 5, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original John Mullett, D.S.

Mon: Wood Post

Access: B Oak 8 N62°W 152

B Ash 9 S8°W 142

APPROVED

County Remonumentation
Peer Review Group

NCC
31 OCT 97

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I re-established this corner position using the single proportion method between corners M-9 and M-11. This location falls in the North & South fence line between Section 25, T6N-R2E, and Section 30, T6N-R3E. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Set a standard Shiawassee County Harrison marker, stamped "Remon 24622" at the location described above. The marker is witnessed by the following accessories:

N20°E 5.54'	Set N&T #24622 in W face 24" Y. Birch
N20°W 13.12'	Set N&T #24622 in E face 18" Hickory
N80°E 6.08'	Set N&T #24622 in N face 6" Ash
S25°W 8.55'	Set N&T #24622 in SE face 6" Ash


Signed by

Mark L. VanRaemdonck

Date OCT. 28, 1997

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983



LIBER 1, 2 DC