

SURVEY & REMONUMENTATION

DEC 02 1993

COMMISSION

1993 Remonumentation program LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
TUSCOLA
(County)

Located in: JUNIATA TOWNSHIP
Corner Code ##

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>12N</u> R <u>8E</u> | <u>M-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD
LIBER NO. _____ PAGE NO. _____
FILING NO. 7411979
93 OCT 22 PM 2:44
JUNIATA TOWNSHIP
TUSCOLA COUNTY
REGISTER OF DEEDS

I, Kenneth D. Dunton, in a field survey on July 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1821 G.L.O. Notes	Aug., 1973 Act 74 Juniata Township, Page 14 by David T. Rowe,
Joseph Wampler, D.S.	R.L.S. #11192. Found 1 1/4" pipe.
Set 1/2 mile post	South 88.26' 1 1/4" pipe at West 1/4 corner, Sec. 7, Indianfields Township.
Ash 16" S37°W 8.58'	North 5.5' fence list West.
Ash 15" N75°E 3.30'	(this corner incorrectly recorded as corner M-4)

Note: Section A. continued on back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and accepted 1" pipe (bent) dug below pipe and found no other evidence.
Dug at split of measured mile and found no evidence of corner.

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Removed 1" pipe and set standard monument with 2" brass cap stamped corner M-2, T12N-R8E.
S00°13'40"E 45.00' found 5/8" re-rod at centerline of o. h. power line E. & W.
S00°12'20"E 88.28' found 1 1/4" iron pipe @ apparent cor. A-4, T12N-R9E.
S37°30'W 65.85' set T.C. Re-mon. tag & spike over #11192 tag in SE face S. tower leg.
S47°15'W 54.11' set T.C. Re-mon. tag & spike over #11192 tag in SE face N. tower leg.
N47°00'E 74.69' set T.C. Re-mon. tag & spike over nail & disc in N. face p. pole.
N69°21'W 11.15' found p. k. nail in S. face of 6" wood corner post.

Signed by [Signature] Date Oct. 11, 1993
Surveyor's Michigan License No. 23503

APPROVED
10-11-93

[Signature]

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
FEB. 1983



Continued from Sec. A. on front of this form.

Nov. 2, 1988 Act 74, Juniata Township, Page 50 by Stephen J. Szyszkoski, R.L.S.
#33986. Found 1" pipe.

S40°W 65.68' found tag #11192 in p. p.

S45°W 53.97' found tag #11192 in p. p.

S80°E 29.60' set p. k. nail in SW face 6" dia. wood fence post.

N70°E 18.11' set p. k. nail in S. face 6" dia. wood corner post.

North 5.5' fence line West.

South 88.26' 1 1/4" pipe at W 1/4 cor. Sec. 7, T12N-R9E.

