

NOV 15 1994

LIBER 4 PAGE 178 COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Nov 4 4 13 PM '94

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Hartford Township

Van Buren County

Located In:

Corner Code =#

Mark A Smith  
VAN BUREN CO  
REGISTER OF DEEDS

1. Public Land Survey T 3S R 16W B-11  
S 1/4 Post Sec 30 T R  
T R  
T R
2. Property Controlling S T R  
in Section S T R
3. Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Donald R. Gilchrist, in a field survey on 11/2/94, 19 , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Gov. Wit. of 1830: Set 1/4 post at 40 ch.; 11" Beech S 23° W 5 lk.; 20" Beech N 61° W 20 lks. April 10, 1870, A.J. Pierce, CS, noted both wit. stumps removed. Put down good stake. In the 1940's & 50's T.A. Smith, CS, & W.Q. Smith, CS, both show distance to cor. at 2635.34'. In 1990 G. Mitchell fd. 1" pipe & Measured 2634.08' to SE corner; SE cor. Garage NW 144.8'; C/L road N 2'. On 6/23/92 J.C. Hunt fd. 5/8" iron in C/L gravel rd.; Survey recorded in SE cor. Liber 9 pg. 347.

At meeting of Peer Group on 10/21/92, approval was given to re-set corner. On 10/22/92, fd. 5/8" I.R. in centerline of gravel road as noted above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10/18/94 D.R. Gilchrist, C.S., fd Harrison Marker paved over last year. Set mon. box over. Approved at the 11/2/94 Van Buren County Peer Group Meeting and is accepted as a careful and faithful perpetuation of the position of the Original Government Corner.

Ratified by Peer Group in  
accordance with P.A. 345 of 1990


Van Buren County Surveyor

D.R. Gilchrist

Date 11/4/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Fd. Harrison Marker, set Mon. Box over.  
N 05° W 47.40' nail E face 10" dia. Apple  
S 35.73' nail E face twin 12"-8" d. tree  
N 80° W 141.19' C/L tel. cable box  
S 80° E 141.56' C/L tel. cable box  
N 50° W 144.20' SE cor. garage  
Measured dist E 2634.08'



Signed by Donald R. Gilchrist

Date 11/4/94

Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583