

SURVEY &
REMONUMENTATION

APR 25 1995

FILED

COMMISSION

5 1/4 SEC. 31

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 22 9 03 AM '94

For corners in PORTER TWP.

VAN BUREN
(County)

Located In:

Corner Code ##

1. Public Land Survey T 4 S R 13 W B-13
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Allen H. McMachen a field survey on December 17, 19 94,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 - William Brookfield, D.S.
30" W. Oak N. 51° E. 55 lks.
30" W. Oak N. 34° W. 83 lks.

± 1910 - W.H. Goss
Stone


1923 - T.A. Smith
Found Stone 6" below surface, cut "X" on top.
Fence line running North is East about 66' & on West side of driveway
center of 12" Hick. N. 10° E. 85.8' center of 15" Maple N. 45° W. 97.7'
center of 20" Oak N. 12° W. 81.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron bar per previous witnesses.
Iron was approved and authorized by the Van Buren Co. Remonumentation
Peer Group.

Notified by Peer Group in
accordance with P.A. 345 of 1990
Van Buren County Surveyor

Date 12/21/94 DRG



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" Iron rod is accepted as a careful and faithful reestablishment
of the original corner. Removed Iron and placed Standard Van Buren County
Section Corner Monument and monument box over.
Accessories:

Nail & Tab in 16" Oak N. 30° W. 75.71'
Nail & Tab in Twin 28" Oak N. 30° E. 37.35'
Nail & Tab in 6" Box Elder S. 50° E. 60.48'
Nail & Tab in Utility Pole S. 40° W. 53.12'
66' E. of brush line to North

Signed by Allen H. McMachen Date 12/21/94
Surveyor's Michigan License No. 16935