

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 24 N. R. 10 W.	G-7; G-8; G-9
2. PROPERTY CONTROLL- ING IN SECTION_____	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 18, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-7 Found 1" pipe in center of E-W gravel road. Corner fits county road commission witnesses.
- G-8 Drove 1½"x20" rod equidistant and on line between found section corners to N & S.
- G-9 Found nail and washer over strong magnetic attraction in center N-S blacktop county road per county road witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7

Found 1" pipe  
SE cor. of brick house N18°E 47.8  
SW cor. of brick house N21°W 61.3  
8" Maple S54°W 70.25  
12" W. Pine S62°E 151.45  
Set cedar post w/loc. tag  
Due S 33.0

G-8

Drove 1½"x20" Rod  
5" R. Pine S72°E 61.00  
4" Twn. Maple S45°E 61.75  
9" B. Cherry cluster S73°W 98.90  
on Ctr. of N-S b'top co. rd.  
Set cedar post w/loc. tag  
Due E 33.0

G-9

Found nail and washer  
4" Elm N25°W 45.00  
NW cor. of house S48°E 163.0  
4" J. Pine S53°W 58.36  
6" R. Pine N54°E 93.15  
on ctr. co. rd. N-S-E

SIGNED BY

Carl F. Roser

DATE

10-31-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY


CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

GREENWOOD TOWNSHIP  
WEXFORD COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET