

Wexford Co. ~ Hanover Twp.  
**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>24</u> N. R. <u>11</u> W.	G-11; G-12; G-13; H-12.
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		
		REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 8, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~XX~~  
C. (continued)

H-12

Set 1" x 6' pipe & ced. post w/loc. tag	
3" S. Pine N60W	23.75'
7" R. Pine N65E	81.47'
6" R. Pine N85E	104.76'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-11 Recovered 'Fargo' corner of record. Corner recently used by RLS Walt Fraser.
- G-12 Recovered 'Fargo' corner of record in center N-S gravel road. Corner recently used by RLS Walt Fraser.
- G-13 Recovered 'Fargo' corner of record.
- H-12 Established center of Sec. 34 at intersection of  $\frac{1}{4}$  lines. Corner falls in old E-W fence. Old corner fence post with fences E&W and N&S for short distance is east of center of Section, 68'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11			G-12			G-13		
Fd. Fargo pipe, stk. & butter dish; added std. Wexf. Co. mon. & ced. post w/loc. tag			Fd. 1" pipe & butter dish & old stk.; added std. Wexf. Co. mon.			Fd. $\frac{1}{2}$ " rod, Fargo pipe & butter dishes; added std. Wexf. Co. mon.		
5" Cedar	N10E	11.9'	21" Maple	S73E	39.30'	11" R. Pine	N25E	81.45'
5" Cedar	S77E	10.9'	31" Maple	S50W	73.61'	P. Pole	S54W	63.95'
9" Cedar	S19W	20.9'	39" Maple	N31W	61.70'	24" Maple	N69E	81.62'
4" Cedar	S39W	13.0'	Set ced. post w/loc. tag			Ctr. E-W Co. Rd.		
			Due E	33'		Due N	2'	
			Fence W. is 16.5' South			Ctr. N-S Co. Rd.		
						Due E	6'	
						Set ced. post w/loc. tag		
						N45E	47'	

(continued)

SIGNED BY Carl F. Roser DATE 11-7-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO.



# CORNER NUMBERING CODE DIAGRAMS FOR IDENTIFYING LAND CORNER RECORDATIONS AND INDEXING

FOR PUBLIC LAND SURVEY CORNERS IN THE  
T. 24 N, R. 11 W. (MENTIONED OVER)

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Apply letter prefix for corner points encircled above  
for identifying corner recordation numbers over.

FOR PROPERTY CONTROLLING AND MISC.  
PROPERTY CORNERS WITHIN THE SECTION  
(MENTIONED OVER AND EXCLUDE LOT CORNER)

				2	
3	4	5	6	7	
	8		9		
10	11	12	13	14	
	15		16		

1. Above coded numbers are positioned on 1/16 fractional lines of the section.
2. Township corner code numbers shall be applied to corners of above typical section not numbered.
3. Miscellaneous property corners within a section, located at points other than numbered above, shall be referenced to at least two of above corner code numbers.
4. Private claim corners to be tied to rectangular land corners if possible — sketch required below.

EXPLANATORY SKETCH IF NECESSARY -- BELOW